

Lori Allen, AD for KPNO



UC Tucson May 16-17 2017





KPNO 2017 Headlines

- Science highlights
- Mayall-4m & WIYN-3.5m status
- Major projects at Mayall and WIYN, status
 - DOE+NSF Dark Energy Spectroscopic Instrument (DESI)
 - NASA+NSF Exoplanet Observational Research (NN-EXPLORE)
- Infrastructure improvements









Recent visit by members of Heising-Simons Foundation

UC Tucson May 16-17 2017



The Deep and Wide Narrowband (DAWN) Survey J. Rhoads (ASU)

- 1.066 μm detection of Lyman- α emission lines from galaxies at z=7.7
- Also detects ELG at z=0.6 using Balmer H α
- Improve our understanding of reionization history



Left: Comparison of a small region of the DAWN survey's narrowband image of the EGS field (upper), and the corresponding DAWN J-band image (lower). Emission line sources are circled. The emission line source farthest left (east) is the z = 7.73Ly- α emitting galaxy first identified by Oesch et al. (2015).



Right: H-a luminosity function for the DAWN survey (from Gonzalez et al. 2017) compared to the HiZELS (Sobral et al. 2013) and New Ha (Ly et al. 2011) surveys

UC Tucson May 16-17 2017







Left: Hardegree-Ullman (U. Toledo). M-Dwarfs in Kepler field with chromospheric activity (to assess habitability) detected through high S/N Hydra spectra.

Right: Nicole Colon (NASA ARC). WHIRC data (2mmag precision) to confirm and characterize K2 exoplanet transit.



NN-EXPLORE Publications:

- Hartman, J. D., et al. "HAT-P-65b and HAT-P-66b: Two Transiting Inflated Hot Jupiters and Observational Evidence for the Reinflation of Close-in Giant Planets, 2016,AJ,152,182H [WIYN 3.5m +WHIRC]
- Cauley, P.W., et al., "A Search for H-alpha absorption around Kelt-3 b and GJ 436 b", 2017, AJ, 153, 81C [WIYN + HYDRA]



Down time, Mayall





7

2,5



- Need work space for min 12 people
- Room for 15
 - 5 along inner wall
 - 10 in two "bays" along outer wall
- Also have kitchen and conference table for 8 in adjoining room
 - With videoconf ability
- Now have 8 screens up high for general interest displays +2 in conf room (cables will be stowed)
- Furniture arriving (tables are in)
- Used in ProtoDESI
 - Led to improved layout

New U-floor Control Room Nearly Done





Coming 2019 → DESI @ KPNO Mayall 4-m



Images: M. Levi, DESI Project Director





- Recent & upcoming DESI milestones
 - WBS 1.9 FDR (28 Feb-1Mar): AIT&C
 - Mayall shutdown starts 13 November 2017
 - Mayall ready for DESI h/w install 23 March 2018
 - Corrector installed 24 May 2018
 - Focal plane assembly installed 13 Dec 2018
 - Start of commissioning 8 Feb 2019
 - Commissioning complete 28 May 2019





KPNO engineer Derek Guenther (left) and safety officer Tammie Lavoie(right) studying process for stringing fiber optic cables from prime focus down the telescope truss.



DESI hardware



UC Tucson May 16-17 2017

Images: M. Levi, DESI Project Director



Imaging survey for DESI targeting: MzLS





Down time, WIYN





Balancing and re-alignment of mount (July 2016) resulted in significant improvement in telescope pointing and tracking

Pointing residuals: Figure at right shows measured pointing performance in January 2015 (top) and September 2016 (bottom). Top: Inner circle is 34" RMS Bottom: Inner circle is 3" RMS

WIYN Performance







New science capability at WIYN



[7 ົບ 0.9 New narrow band filter @ 695 nm for emission-line surveys olor Region WCS Analysis 0.3 × 0.2 £ **1** 0.1 0.0 6,800 6,825 6,850 6,875 6,900 6,950 6,975 7,000 7,025 7,050 7,075 7,100 6.925 5 2:37:51.549 + 27:31:29.43 hysical 20088.000 4524.000 range 20088.000 4524.000 rame 1 1.000 0.000 2:37:51.927 +27:31:33.24 Wavelength (A) 20043.000 20043.00 4558.000

Left: Narrow band filter. Right: Narrow band - continuum (r'), quicklook reduction

1.1

1.0

0.9

0.8 07

0.6 0.5 0.4

0.3

0.2

0.1



Clockwise from above: installing new ring on secondary baffle, tertiary baffle, tertiery baffle

Stray Light Mitigation at WIYN

Below Left: no baffles, strong straylight in LL corner, 20% effect.

Below Right: *w/* new baffles, some internal reflections / gradient left, <4% level, average out *w/* rotation.







Partnership for Exoplanet Discovery and Characterization

NN EXPLORE

Derived from Tohono O'odham word "to see"



Extreme Precision Doppler Spectrometer Motivation: TESS, K2, etc. **Mission**: determine masses of Earth-like planets

Requirement: < 50 cm/s Goal: ~ 10 cm/s

Instrument for the community Operations start 2019 Q2

PI: S. Mahadevan (PSU)



- NEID milestones
 - Spec DDR November (passed)
 - Port, Facilities DDR (Jun 2017)
 - Facility mods complete (Jan 2018)
 - Port Adaptor install (May 2018)
 - PA commissioned (Aug 2018)
 - Spec arrives (Sep 2018)
 - Spec installed (Oct 2018)
 - Spec commissioned (Jan 2019)
 - Spec LB comm / ORR (Apr 2019)
 - NEID operations (Apr 2019)



with vacuum chamber



New DIMM (seeing monitor) going in, Spring 2017

- DIMM telescope and mount, initial testing in Tucson lab
- Dome already installed and waiting







End of Presentation





Background Slides

- Remaining slides chronicle improvements to the Mayall facility over last 2 years
 - Some improvements in preparation for DESI
 - Others to ensure long-term viability of telescope and dome



Infrastructure improvements

- Electrical system upgrade scheduled (21-25 August)
 - Second half of mountain-wide power distribution system upgrade
 - Will replace 50-year old switch gear
 - Power outage for much of mountain (generator power for essential staff functions)
 - Tenants notified in mid-February



The first half of the electrical system upgrade, completed last year, includes new switch gear in "rock house" below Mayall



- New 80kW UPS
- Serves 3 existing, 4 new panels
 - Coudé room (incl PF and telescope top end, for ADCs, Cal lamps, hexapods)
 - U-Floor
 - Computer
 - Main Floor
- Wiring and UPS
 done Summer 2016

KP-9001,2,3,9: Done





- Glycol System: 3 lines needed inside Coudé room
 - Spectrograph "shack" climate control
 - LPT chiller
 - Prime Focus cooling loop (backup only)
- Mirror cooling lines just on dome side of Coudé room wall
- Taps installed there (1.5-inch) will serve 3 x 1-inch taps inside room
 - Install 1-in taps in room when equipment locations determined
- TCS Interface: DESI-0473 gives requirements:
 - DESI-1132 describes implementation
 - DESI-1949 describes results of successful on-sky tests 21-22 Jan 2016
 - Used throughout ProtoDESI campaign (DESI-2561)

David Sprayberry / WBS 1.9 FDR

KP-9004, 5: Both Done



UC Tucson May 16-17 2017



KP-9006: Planned

- 10Gb/s backbone on fiber
- Nodes in Computer room, Coudé room, U-floor annex, telescope
 - Telescope node for PF, Cass, and top ring (cal lamp control)
- Each node
 - Receives 10Gb/s via fiber backbone
 - Distributes 1Gb/s via Cat 5/6 and RJ-45 to use points
- Equipment will be ordered "just in time" to maximize price vs. performance
- First node needed: Coudé room before "early shack" goes in
 - Will do whole network at once, "early shack" is pacing item
 - Aiming for completion Aug 2017



- Added to 1.09.02 after PDR
- Design Complete
- Parts Made
- Installation underway
 - Fixed components being done



KP-9010: Underway





Other DESI Prep Tasks: Large Coudé Room Preparation Underway

- Cut out obstructions (safely)
 - e.g., 2100-AD-015-0051, and JHA (see DESI-2666, 2667)
- Cut hole for fiber pass-thru
- Clear space for "shack"







- Corrector re-assembly, alignment
 - Same process for DECam
 - Frame from FNAL, rotary table from UCL
- NOAO provides
 - Tent to enclose it (spec'd out, will be ordered in March 2017)
 - Paint floor
 - Adequate crane (small mobile crane)
 - Electric power, air (present already)

Garage Prep In Hand



David Sprayberry / WBS 1.9 FDR



- M1 Cover extensions: designed, materials ordered
- Top End Cooling (up to new top ring): designed, parts ordered
- Zenith Work Platforms: designed, materials ordered and custom parts made

M1, Cooling, Platforms



Mirror Lift Upgrade





David Sprayberry / WBS 1.9 FDR

UC Tucson May 16-17 2017

AURA



TCS Modernized: Encoders, Servos, Software

- Finished Summer 2015
- In full-time use since then
- All-sky pointing errors < 3 arcsec rms (was 18" rms)
- Open-loop tracking similarly good (< 1mas/s)
 - Allowed for reduction in DESI guider update rate req't
- Used for:
 - TCS-ICS testing
 - MzLS Semester 2016A
 - ProtoDESI





Upper Dome Shutter Drive Gearbox

• Old unit was under-rated, badly worn, likely to fail soon





- 4MAPS Before
 - 40s to settle
- 4MAPS Now
 - < 5s to settle
- Significant reduction in telescope overheads during DESI inter-exposure sequence
 - Average exposure 20min
 - Reconfiguration time:
 - Reqt 2 minutes
 - Goal 1 minute
 - This is ~ 2.5% gain in efficiency or survey duration margin
- Finished Summer 2016



4MAPS



E-Stop System Upgrade

- Extended
 - To places previously not properly covered, e.g. mirror lift
 - To places not covered at all, e.g. U floor
- Brought up to modern safety and engineering standards
- Fully tested
- Implements all required power cuts and telescope brake applications



David Sprayberry / WBS 1.9 FDR



New Chiller

- Same 45T capacity
- Same dual-circuit flexibility
- Same control software
- Will be plumbed for quick switchover





Astrometry Camera will be available for DESI

- Mounts to top ring, 8 deg x 6 deg FOV
- Initial tests got solutions from Astrometry.net in < 0.2 sec average (next slide)
- Can help shorten initial pointing tests for DESI, also do ongoing real-time checks





Sample Camera Image as processed by Astrometry.net





Primary Mirror Temperature Control Upgrade Underway

Current PMTC Architecture

- Goals:
 - Replace old electronics
 - Retain existing infrastructure where possible
 - Minimize downtime
 - Complete before DESI installation starts (end of Summer 2017)
 - Provide full control and status to user software
 - Improve status displays and logging
 - Add sensors for redundancy and analysis
 - Provide platform for improvements in cooling









The Mayall has been rejuvenated!

- We repainted the dome Summer 2016
 - Lo-mit coating for improved thermal performance
 - Addressed long-term maintenance need

